



**MISHRA DHATU NIGAM LIMITED  
P.O.KANCHANBAGH, HYDERABAD**

**Part-II (PRE - PRICE BID)**

**CONSTRUCTION OF COMPOUND WALL FOR  
MULTI LEVEL CAR PARKING ON REAR SIDE OF  
FIRE STATION  
MIDHANI,  
KANCHANBAGH, HYDERABAD-58.**

**PURCHASE DEPARTMENT**

Tender Notice No: MDN/PUR/AP2061070/ADVT/064/17-18

Date:08-06-2017

To,

Dear Sir,

**Sub: - CONSTRUCTION OF COMPOUND WALL FOR MULTI LEVEL CAR PARKING ON REAR SIDE OF FIRE STATION, MIDHANI - req**

1. Please find enclosed herewith a Tender Enquiry for the above, you are requested to furnish your offer in a sealed cover superscripting the envelope with name of work and last date of submission, along with EMD of Rs 38,600/- & Tender Fee Rs. 1000/- online through link <http://ebs.in/midhani/public> or visit midhani website [www.midhani.com](http://www.midhani.com)> purchase > Tenders > Tender fee, EMD fee (Earnest Money Deposit) and security Deposit –ONLINE PAYMENT. The tenders without EMD amount will be rejected; request for adjustment from pending bills will not be entertained. . Please confirm whether you are MSME Unit or MSME Unit owned by SC/ST Entrepreneur. If yes, please submit latest valid documentary proof for extending benefits as per government guidelines (Estimated value of work is Rs.15.43 Lakhs).
2. Tender shall be submitted in tender box kept at corporate office on or before 30-06-2017 up to 10.30 hrs.
3. The period of completion of job will be 120 days from the date of handing over of site. Time is essence of the contract; contractor has to mobilize materials & labour to complete within 120 days time period.
4. The tenderer shall inspect the site of work and understand the scope of work before quoting. No extra amount will be paid on account of misunderstanding either in scope of work, specification, drawings, site conditions etc.
5. All materials required for the work shall be arranged by the contractor unless until specified in Bill of Quantities.
6. The work shall be carried out as per MES-SSR-2009 specifications.
7. This is an item rate contract and the quantities are approximate, but payment will be made only on actual work done based on joint measurement.
8. Four R. A Bills and one Final Bill will be paid. The contractor has to furnish all material bills along with each bill (if any).
9. R.A Bill will be paid within 15 days from the date of certification of Engineer-in-charge. However, Final payment will be made within 30 days after satisfactory completion of work and certification by Engineer-in-charge.
10. a) **Security Deposit (S.D):** The successful tenderer has to submit 5% of Work order value as a security deposit online through link <http://ebs.in/midhani/public> or visit midhani website [www.midhani.com](http://www.midhani.com)> purchase > Tenders > security Deposit – ONLINE PAYMENT/ Bank Guarantee at the time of entering / signing the contract. Further, EMD deposited will be adjusted in 5% Security Deposit & the security

EMPLOYER

CONTRACTOR

deposited will be released after satisfactory completion of work and after certification of Engineer-In- Charge.

b) **Retention Money** : A sum of 5% of gross value of work order will be deducted from each running bill and final bill. The same will be released after the completion of defect liability period of 12 months and after certification of Engineer –In- Charge. Also, contractor can submit Bank Guarantee for equivalent amount in the prescribed format issued by nationalized or scheduled bank and same shall be valid for defect liability period + 3 months claim period.

11. The security and safety rules of MIDHANI to be followed. The contractor shall take care of all labour laws regarding minimum wages, ESI, PF, C.A.R. Policy, Group Insurance etc., Midhani is no way responsible in this respect. Midhani is not liable for any claim in respect of any accidents during the work.
12. (a) MIDHANI reserves the right to operate partial or delete any item specified in BOQ without any compensation to contractor for the items un-operated or deleted.  
  
(b) If at any time after acceptance of the tender MIDHANI feels that for any reasons whatsoever, if the whole or any part of the contract services is not required to be carried out, notice shall be given in writing of the fact to the contractor and upon receipt of such notice, the contractor shall stop the execution of such services as indicated in the notice forthwith. The contractor shall have no claim to any payment of compensation or otherwise whatsoever on account of any profit or advantage which he might have derived from the execution of the services in full, but which he did not derive in consequence of the foreclosing of the services / contract. Contractor shall be paid at contract rates for the full amount of the work executed including such additional services as may be rendered necessary by said foreclosing.
13. Any new items (viz. supply of material, labour, skilled works etc) will be paid as per (a) or (b) whichever is less:
  - a) As per MES-SSR 2010 rates with applicable Percentage Index at that time.
  - b) As per market rate analysis.
14. The contractor should not cause any loss or damage to MIDHANI property/or personnel, if any loss or damage is caused the cost of the same will be recovered from the bills by MIDHANI, which will be final.
15. The quantities are subjected to  $\pm 20\%$  variation and the contractor has to carry the work on the same rates, terms and conditions within the variation limits prescribed. In case if the quantities exceeding beyond 20% of the BOQ, the exceeding quantities beyond 20% shall be executed at the rates lowest among the tender .
16. If the contractor fails to receive the work order within a week time from the date of intimation to him or if the contractor does not start the work within 3-7 days from the date of handover of site, or if the work is abandoned / stopped without bringing proper notice to Engineer-in-charge, the contract will be terminated and balance work will be carried out at the cost and risk of contractor.
17. Liquidated Damages: - a) If the work is not completed within stipulated time, liquidated damages at 1% per week delay up to maximum of 10% total value of work will be deducted.  
b) If the delays are not attributed to the contractor, the competent authority holds the right to waive off the L.D or reduce the L.D as the case may be.
18. Midhani reserves the right to penalize

- a) If the contractor fails to submit the 5% Security deposit within the stipulated period, then penalty of Rs 1000 per day maximum of 10,000.00 will be collected and further delay will empower MIDHANI to termination of contract and apply risk purchase.
- b) If the contractor fails to receive the work order within 3 days of intimation, then a penalty Rs 500 per day will be levied subjected to maximum of Rs 5000.00. Further delay will empower MIDHANI to termination of contract and apply risk purchase.
- c) Contractor has to maintain "HINDRANCE REGISTER" which is to be certified by both MIDHANI Site engineer and contractor engineer before release of final bill.
19. The offer shall be valid for 3 months from the date of opening of tender.
20. Interested parties may attend tender opening on 30-06-2017 at 11:00 hrs.
21. Incomplete or partially filled tenders will be rejected. Also, conditional offers are liable for rejection. MIDHANI reserves the right to accept or reject any or all tenders without assigning any reasons.
22. Contractor has to maintain site record, hindrance record, record for steel, cement etc. and employ qualified & experience Engineer at site .
23. Site has to be cleaned by the contractor before handing over to MIDHANI after completing the work. The final bill will be processed only after obtaining site cleaning certificate from the Engineer-in-charge.
24. The Earnest money deposit can be encashed if the tenderer withdraws his tender proposals / modifies / changes / alters / impairs / derogates the tender document on his own after the first cover is opened or within the subsistence of the validity period of offer or fails to accept the Letter of Award (LOA) issued by MIDHANI or fails to submit security deposit or fails to turn-up and execute contract agreement or fails to commence the work as per LOA. Such bidders will be banned subject to action as may be deemed fit. In case of unilateral revision or withdrawal of offer by the bidder as above, shall also result in rejection of bid without notice. If there is any authentic information about the intending tenderer having formed a cartel / submitted Non-earnest bids, the tender will be cancelled and the Earnest Money Deposit of all the tenderer shall be forfeited, besides initiating actions like banning as may be deemed fit.
25. **Contractor has to quote overall  $\pm$  percentage on this pre-price bid. The accuracy shall be up to two decimals.**

Yours faithfully,  
For Mishra Dhatu Nigam Limited

**T.Raghuram**  
**Addl. General Manager (I/c Purchase)**

- DECLARATIONS: - 1) I have seen the site and understood the full scope of work, specified in tender, BOQ, etc.
- 2) I agree to return all the documents along with this offer.
- 3) I have taken into account of points circulated in Minutes of Pre bid Meeting circulated on MIDHANI website, if posted

CONTRACTOR  
SIGNATURE AND SEAL

P.S;- All Parties shall attend pre bid meeting on 13-06-2017 at 11.00Hrs at Purchase Department.

EMPLOYER

CONTRACTOR

**Construction of Compound Wall for Multi Level Car Parking on Rear Side of Fire Station , MIDHANI**

SI.No	Description of work	unit	Quantity	Rate	Amount
1	Earthwork i Excavation by mechanical means (hydraulic means) / manual means over area including disposal of excavated earth, lead upto 50 m from natural ground level and backfilling of soils wherever & whenever required as directed by E.I.C. Disposed earth to be leveled and neatly dressed.				
a	Hard soil	Cu.m	210.00	178	37380
b	Hard rock	Cu.m	50.00	356	17800
2	Demolition of stone or brick masonry including all quoins, arches, pillars etc built in cement mortar including removing mortar from and cleaning of stone from masonry. The cost includes separation of serviceable materials from the unserviceable; stacking the serviceable materials within 100m and disposal of unserviceable material, debris and rubbish to a distance not exceeding 100m as directed by the EIC.	Cu.m	9.00	1602	14418
3	Carriage/Carting of excavated soils/rock by mechanical transport including loading, unloading, stacking and leveling for the required areas upto 1.0 km.				
A	Soil	Cu.m	126.00	178	22428
B	Rock	Cu.m	50.00	445	22250
4	Providing & laying Plain Cement concrete in foundations filling and mass concrete Type C2 1:3:6 (40mm graded aggregate) including mixing, placing, compacting, ramming and curing.	Cu.m	11.00	3382	37202
5	Providing & Construction of random rubble, uncoursed, well bonded, bedded and solidly hearted, built in cement mortar (1:6) at all heights and levels including the cost of scaffolding etc.	Cu.m	280.00	2581	722680
6	Providing cement concrete(1:2:4) in copings on top of walls including shuttering, scaffolding etc slightly rounded or chamfered angles and throating, as directed	Cu.m	8.00	3115	24920
7	Providing Raised Tuck pointing to random rubble, uncoursed with cement mortar (1:4) including scaffolding etc at all heights and levels.	Sq.m	925.00	266.11	246151.75
8	Providing & Plastering in 15mm thick in C.M(1:4) firmly applied to RCC pillars and finished to get smooth even & fair surface at all heights and levels including the cost of scaffolding etc.	Sqm	21.00	267	5607
9	Providing & laying of Design mix concrete M25 RCC corresponding to IS456 with minimum cement content of 380 Kgs per 1 Cum of concrete ( any ± variation in the cement consumption as pper mix design is allowed) using Ready mix concrete (RMC) with 20mm size graded machine crushed hard granite metal( coarse aggregate)( consisting of nominal size metal of 20mm, 13.2/12.5mm , 10mm & 6mm) from approved	Cum	8.50	6218.1	52853.85

EMPLOYER

CONTRACTOR

	quarry including cost & conveyance of all materials like cement, fine aggregate( Sand) , coarse aggregate , water etc to site and including charges , sales & other taxes on all materials , centering using steel scaffolding pipes, jack drops, wallers, foot plates, brackets , steel centering plates etc.. including all operational , incidental and labour charges such as weigh batching, machine mixing, laying concrete , curing etc and overheads & contractors profit complete but excluding cost of steel ans its fabrication charges for finished item work.				
10	Providing & Fixing and placing Fe-500 bar-TMT reinforcement in RCC works complete as per drawings and technical specifications for bars below 36mm dia including over laps and wastage, where they are not welded including cost and conveyance of steel, binding wire etc., lifting charges of steel, placing in position, tying with binding wire, all tools etc., and overheads & contractors profit complete for finished item of works.	Kgs	600	62.18	37308
11	Supply, fabrication and erection of Mild steel for framing work in doors/gates etc with MS angles, flats, plates, welding mesh partition etc (Including cutting, bending, welding electrodes) complete. (At all heights & levels and as per instruction of Engineer-in-Charge). The cost includes one coat of Zinc chromate primer paint and two coats of enamel paint.	Kgs	1905	70.31	133940.55
12	Labour Charges for fixing Barbed wire fencing with Galvanized. 2 strand, steel barbed wire 2.24mm dia barbed with 2mm dia barbs at 75mm spacing's and straining and fixing to any type of standard rails straining bolts, including, securing or tying at crossings with and provision of galvanized mild steel wire, staples or steel pins, etc. as directed.( material will be provided by MIDHANI)	RM	1200	23.14	27768
13	Supply and Fixing of 2mm thick FRP plain sheet to steel gate/door etc including the cost of making holes, bolts, nuts, washers etc complete.	Sqm	20.00	489.50	9790
14	Providing & Boring 300mm dia bore piles upto 3.0m depth including M15 Concrete but excluding reinforcement	No's	50	2400	120000
15	Supply of Labour				
A	Unskilled labour	No's	15	400.50	6007.50
B	Skilled labour	No's	10	534	5340
			<b>Total in Rs.=</b>		<b>15,43,845</b>
			<b>Percentage + / -</b>		
			<b>Grand Total Rs=</b>		

(In Words..)

EMPLOYER

CONTRACTOR