



**MISHRA DHATU NIGAM LIMITED  
P.O.KANCHANBAGH, HYDERABAD**

**Part-II (PRICE BID)**

**Excavation of Hard Soil / Rock in Wide Plate Mill,  
MIDHANI,  
KANCHANBAGH, HYDERABAD-58.**

**PURCHASE DEPARTMENT****Tender Notice No: MDN/PUR/AP58/EADVT/120/17-18****Date:-10-08-2017****To,**

Dear Sir,

**Sub: - Excavation of Hard Soil / Rock in Wide Plate Mill, MIDHANI, - req**

1. Please find enclosed herewith the Tender Enquiry for the above work you are requested to furnish your offer through online <http://eprocuemidhani.nic.in> before last date of submission, along with Tender Fee Rs. 1000/- , along with EMD of Rs 3,11,200.00 online through link <http://ebs.in/midhani/public> or visit midhani website [www.midhani.com](http://www.midhani.com) > purchase > Tenders > Tender fee, EMD fee (Earnest Money Deposit)–ONLINE PAYMENT or Bank Guarantee confirmed by bankers of bidders favoring MIDHANI through a Nationalized Bank/ Scheduled Commercial Bank en-cashable in INDIA . The tenders without EMD/tender fee amount will be rejected; request for adjustment from pending bill will not be entertained. Please confirm whether you are MSME Unit or MSME Unit owned by SC/ST Entrepreneur. If yes, please submit latest valid documentary proof for extending benefits as per government guidelines. Estimated Value of work is Rs 1,24,48,000.00.
2. Tender shall be submitted on or before **31-08-2017** up to 10.30 hrs.
3. The period for completion is **75 days for Module-I & 45 days for Module-II** from the date of hand over of site **for each module** Time is essence of the contract; contractor has to mobilize materials & labour to complete within stipulated time period.
4. **MIDHANI reserves the right to split the tender in to two module viz Module-I & Module-II as per the lowest quotations. No compensation to the contractor for reduction in scope of work.**
5. The tenderer shall inspect the site of work and understand the scope of work before quoting. No extra amount will be paid on account of misunderstanding either in scope of work, specification, drawings, site conditions etc.
6. All tools/tackles/machinery etc & materials required for the work shall be arranged by the contractor unless until specified in Bill of Quantities.
7. The work shall be carried out as per MES-SSR-2009 specifications.
8. This is an item rate contract and the quantities are approximate, but payment will be made only on actual work done based on joint measurement.
9. Three R. A Bills and one Final Bill will be paid for each module. The contractor has to furnish all material bills along with each bill (if any).
10. R.A Bill will be paid within 15 days from the date of certification of Engineer-in-charge. However, Final payment will be made within 30 days after satisfactory completion of work and certification by Engineer-in-charge.

EMPLOYER

CONTRACTOR

11. a) **Security Deposit (S.D):** The successful tenderers has to deposit 5% of contract value as Security Deposit at the time of agreement. This 5% Security Deposit can be submitted online through link <http://ebs.in/midhani/public> or visit midhani website [www.midhani.com](http://www.midhani.com) > purchase > Tenders > security Deposit –ONLINE PAYMENT or can deposit Bank Guarantee from any nationalized bank..The validity of B.G shall be equivalent to contract period plus three months extra. The EMD will be absolved in this 5% security deposit .The 5% Security Deposit will be released after completion of work, Site clearance and cleaning by the contractor duly certified by Engineer- In- Charge.
- b) **Retention Money :** A sum of 5% of gross value of work order will be deducted from each running bill and final bill. The same will be released after the completion of defect liability period of 6 months and after certification of Engineer –In- Charge. Also, contractor can submit Bank Guarantee for equivalent amount in the prescribed format issued by nationalized or scheduled bank and same shall be valid for defect liability period + 3 months claim period.
12. The security and safety rules of MIDHANI to be followed. The contractor shall take care of all labour laws regarding minimum wages, ESI, PF, C.A.R. Policy, etc., Midhani is no way responsible in this respect. Midhani is not liable for any claim in respect of any accidents during the work.
13. (a) MIDHANI reserves the right to operate partial or delete any item specified in BOQ without any compensation to contractor for the items un-operated or deleted.
- (b) If at any time after acceptance of the tender MIDHANI feels that for any reasons whatsoever, if the whole or any part of the contract services is not required to be carried out, notice shall be given in writing of the fact to the contractor and upon receipt of such notice, the contractor shall stop the execution of such services as indicated in the notice forthwith. The contractor shall have no claim to any payment of compensation or otherwise whatsoever on account of any profit or advantage which he might have derived from the execution of the services in full, but which he did not derive in consequence of the foreclosing of the services / contract. Contractor shall be paid at contract rates for the full amount of the work executed including such additional services as may be rendered necessary by said foreclosing.
14. Any new items (viz. supply of material, labour, skilled works etc) will be paid as per (a) or (b) whichever is less:
- As per MES-SSR 2010 rates with applicable Percentage Index at that time.
  - As per market rate analysis.
15. The contractor should not cause any loss or damage to MIDHANI property/or personnel, if any loss or damage is caused the cost of the same will be recovered from the bills by MIDHANI, which will be final.
16. The quantities are subjected to  $\pm 50\%$  variation and the contractor has to carry the work on the same rates, terms and conditions within the variation limits prescribed.
17. If the contractor fails to receive the work order within a week time from the date of intimation to him or if the contractor does not start the work within 3-7 days from the date of handover of site, or if the work is abandoned / stopped without bringing proper notice

to Engineer-in-charge, the contract will be terminated and balance work will be carried out at the cost and risk of contractor.

18. Liquidated Damages: - a) If the work is not completed within stipulated time, liquidated damages at 1% per week delay up to maximum of 10% total value of work will be deducted.  
b) If the delays are not attributed to the contractor, the competent authority holds the right to waive off the L.D or reduce the L.D as the case may be.
19. Midhani reserves the right to penalize  
a) If the contractor fails to submit the 5% Security deposit within the stipulated period, then penalty of Rs 1000 per day maximum of 10,000.00 will be collected and further delay will empower MIDHANI to termination of contract and apply risk purchase.  
b) If the contractor fails to receive the work order within 3 days of intimation, then a penalty Rs 500 per day will be levied subjected to maximum of Rs 5000.00. Further delay will empower MIDHANI to termination of contract and apply risk purchase.
20. The offer shall be valid for 3 months from the date of opening of tender.
21. Incomplete or partially filled tenders will be rejected. Also, conditional offers are liable for rejection. MIDHANI reserves the right to accept or reject any or all tenders without assigning any reasons.
22. Contractor has to maintain site record, hindrance record, record for steel, cement etc.
23. The contractor shall employ minimum one qualified & well experienced Diploma / Graduate Engineer for the supervision of work. Deployment of Engineer at site to be certified by Engineer-In-Charge.
24. Site has to be cleaned by the contractor before handing over to MIDHANI after completing the work. The final bill will be processed only after obtaining site cleaning certificate from the Engineer-in-charge.
25. The contractor shall bear all levies, taxes including service tax, duties etc., payable or arising from/ out of by virtue of or in connection with and / or incidental to the contract or operation(s) or any other part thereof to be performed by the contractor and the contractor shall indemnify and keep indemnified MIDHANI from and against the same or any default by the contractor in the payment there of.

Yours faithfully,  
For Mishra Dhatu Nigam Limited

**T.RAGHURAM**  
**Addl. General Manager (I/C Purchase)**

DECLARATIONS: - 1) I have seen the site and understood the full scope of work, specified in tender, BOQ etc.  
2) I agree to return all the documents along with this offer.

CONTRACTOR  
SIGNATURE AND SEAL

P.S;- 1. All Parties shall attend pre bid meeting on 19-08-2017 at 11.00Hrs in the Purchase Department.

EMPLOYER

CONTRACTOR

| <b>Module - I</b>                            |  |              |            |              |            |               |            |
|--|--|--------------|------------|--------------|------------|---------------|------------|
| <b>BOQ for Excavation of Wide Plate Mill</b> |  |              |            |              |            |               |            |
| <b>S. No</b>                                 | <b>Description</b>   | <b>Units</b> | <b>Qty</b> | <b>Rate</b>  |            | <b>Amount</b> |            |
|  |  |              |            | <b>Rs.</b>   | <b>Ps.</b> | <b>Rs.</b>    | <b>Ps.</b> |
| 1  | Earth work excavation for foundations (Mechanical Means) in all types of soils and deposition on bank for all lifts and with an initial lead of 200m and up to below depths including all operational, incidental charges such as shoring, sheeting, planking, strutting (for slopes 45*)etc., and overheads & contractors profit complete for excavation work. The cost includes subsoil and dewatering rainwater/seepage to keep the excavation dry, levelling and dressing the bottom of excavation to correct level, at all heights and levels. Cost also includes disposal in 200M lead |              |            |              |            |               |            |
| (a)  | From 0.00 to (-) 3.0M  | Cu.m         | 2597.49    |              |            |               |            |
| (b)  | From (-) 3.00 to (-) 6.0M  | Cu.m         | 2350.24    |              |            |               |            |
| (c)  | From (-) 6.00M to (-) 9.0M   | Cu.m         | 618.58     |              |            |               |            |
| 2  | Hard Rock Excavation in foundations and trenches in hard rock with controlled blasting as defined by IS:1200 in both dry and wet conditions including dewatering the subsoil and rainwater to keep the excavation dry, levelling and dressing the bottom of excavation to correct. at all heights and levels. Cost also includes disposal in 200M lead.  |              |            |              |            |               |            |
| (a)  | From (-) 7.0 to (-) 9.0M   | Cu.m         | 1237.16    |              |            |               |            |
| (b)  | From (-) 9.0 to - 12.0 M   | Cu.m         | 830.74     |              |            |               |            |
| (c)  | From (-) 12.00 to (-) 15.0 M   | Cu.m         | 212.16     |              |            |               |            |
|  |  |              |            | <b>Total</b> |            |               |            |
| <b>(Total in words.....</b>                  |  |              |            | <b>)</b>     |            |               |            |

EMPLOYER

CONTRACTOR

| <b>Module - II</b>                           |  |              |            |              |            |               |            |
|--|--|--------------|------------|--------------|------------|---------------|------------|
| <b>BOQ for Excavation of Wide Plate Mill</b> |  |              |            |              |            |               |            |
| <b>S. No</b>                                 | <b>Description</b>   | <b>Units</b> | <b>Qty</b> | <b>Rate</b>  |            | <b>Amount</b> |            |
|  |  |              |            | <b>Rs.</b>   | <b>Ps.</b> | <b>Rs.</b>    | <b>Ps.</b> |
| 3  | Earth work excavation for foundations (Mechanical Means) in all types of soils and deposition on bank for all lifts and with an initial lead of 200m and up to below depths including all operational, incidental charges such as shoring, sheeting, planking, strutting (for slopes 45*)etc., and overheads & contractors profit complete for excavation work. The cost includes subsoil and dewatering rainwater/seepage to keep the excavation dry, levelling and dressing the bottom of excavation to correct level, at all heights and levels. Cost also includes disposal in 200M lead |              |            |              |            |               |            |
| (a)  | From 0.00 to 0 3.0   | cu.m         | 6390.90    |              |            |               |            |
| (b)  | From (-) 3.00 to (-) 6.0   | cu.m         | 3595.95    |              |            |               |            |
| (c)  | From (-) 6.00 to (-) 9.0M  | cu.m         | 490.00     |              |            |               |            |
| 4  | Hard Rock Excavation in foundations & trenches in hard rock with controlled blasting as defined by IS: 1200 in both dry and wet conditions including dewatering the subsoil and rainwater to keep the excavation dry, levelling and dressing the bottom of excavation to correct level, at all heights and levels. Cost also includes disposal in 200M lead.   |              |            |              |            |               |            |
| (a)  | From (-) 6.00 to - 9.0M  | Cu.m         | 447.20     |              |            |               |            |
| (b)  | From (-) 9.00 to - 12.0M   | Cu.m         | 249.60     |              |            |               |            |
| (c)  | From (-) 12.00 to - 15.0M  | Cu.m         | 595.75     |              |            |               |            |
|  |  |              |            | <b>Total</b> |            |               |            |
| <b>(Total in words....</b>                   |  |              |            |              |            | <b>)</b>      |            |

EMPLOYER

CONTRACTOR

